



STRUCTURED WIRE
 HOME THEATER
 STRUCTURED MEDIA
 NETWORKING
 INTERNET SHARING
 VIDEO DISTRIBUTION
 MULTI-ROOM VIDEO
 HOME MONITORING
 MULTI LOCATION STEREO

NEW HOME PLATFORM

- **INCLUDED IN ALL NEW HOMES WITH ALL PLATFORMS**
- 3 CAT 5E RUNS *TERMINATED AT WALL LOCATION ONLY*
- 3, 8 CONDUCTOR GIGAMAX *WALL TERMINATION*
- 3 RG6 “QUAD SHIELD” RUNS *TERMINATED AT WALL LOCATION ONLY*
- 3 QUICKPORT COMPRESSION CONNECTIONS *WALL TERMINATION*
- SECURITY PRE-WIRE: INCLUDES 2 KEYPAD LOCATIONS (CAT 5E), 2 MOTION, 3 DOOR CONTACTS (AWG 22/4 WIRE)
- SPEAKER PRE WIRE (16/2 AWG & CAT 5E): ROUGH IN FOR 1 PAIR OF IN WALL SPEAKERS; CAT 5E AND 16/2 RUN FROM VOLUME OUTLET TO STRUCTURED MEDIA CENTER (SMC); 2, 16/2 RUNS FROM RECEIVER “AMP” AREA TO SMC **(NOT INCLUDED IN SUPREME PLATFORM)**
- 4 RG6 RUNS FOR FUTURE SATELLITE (NON-TERMINATED)
- 2 CAT 5E, 2 RG6, FRONT & REAR DOOR (FUTURE SECURITY CAMERA’S AND NOT TERMINATED)
- 1 AWG 6 COPPER GROUND *IF REQUIRED* (SMC TO DEMARCATION)
- 1 AWG 16 COPPER GROUND *IF REQUIRED* (SMC TO ELECTRICAL PANEL)
- 1.5” PVC CONDUIT FROM ATTIC TO BASEMENT FOR FUTURE WIRE WITH PULL STRING
- ALL RUNS LEFT IN A COIL IN THE SMC AREA (BASEMENT)

<u>SUGGESTED RUNS</u>	
MASTER BED	(1 X 1)
FAMILY ROOM	(1 X 1)
OFFICE/DEN	(1 X 1)
SATELLITE	(0 X 4)
SECURITY	(2 X 0)
CAMERA	(2 X 2)
SPEAKER	(1 X 0)
TOTAL CAT5E RUNS	8
TOTAL RG6 RUNS	9